1601 Maple Ridge Rd, Medina, NY P 800.528.1398 F 585.798.8889 www.takeform.net

Rigid Mounting Template Simpson SETPAC-EZ Epoxy- (1) A0250 tie anchoring adhesive cartridge

And either A, B, C or D set of hardware per below: (2 or more sets are required per Cabinet install)

A. 3/8-16 x 2.75 Steel Anchor 3/8-16 x 1.25 SS SHCS	(4) (4)	900-93980A150 900-92196A626
3/8 SS Lock Washer 3/8 SS Flat Washer	(4) (4)	900-92146A031 900-92141A031
B. 1/2-13 x 3.69 Steel Anchor 1/2-13 x 1.25 SS SHCS 1/2 SS Lock Washer 1/2 SS Flat Washer	(4) (4) (4) (4)	900-93980A170 900-92196A714 900-92146A033 900-92141A033

C.

5/8-11 x 5.75 Steel Anchor	(4)	900-93980A190
5/8-11 x 1.75 SS SHCS	(4)	900-92196A800
5/8 SS Lock Washer	(4)	900-92146A035
5/8 SS Flat Washer	(4)	900-92141A035
D. 3/4-10 x 6.50 Steel Anchor 3/4-10 x 2.00 SS SHCS 3/4 SS Lock Washer	(4) (4) (4)	900-93980A210 900-92196A843 900-92146A036

(4) 900-92141A056

3/4 SS Flat Washer

Level / Caulk Gun / Masking Tape / Tape Measure Protective Bib (cardboard, plastic sheet or drop cloth) Compressed Air Hammer Drill Masonry Drill Bit (see below for bit diameter)

- 1/2" for anchor in "A" set of hardware
- 5/8" for anchor in "B" set of hardware
- 7/8" for anchor in "C" set of hardware
- 1" for anchor in "D" set of hardware

Hex L-Kev


- 5/16" for SHCS in "A" set of hardware •
- 3/8" for SHCS in "B" set of hardware
- 1/2" for SHCS in "C" set of hardware
- 5/8" for SHCS in "D" set of hardware

Place and temporarily secure rigid mounting template on top of existing foundation where sign is to be mounted. Using the template as a guide, drill anchor holes into existing foundation to depth listed (depth does not include template):


- 3" for anchor in "A" set of hardware •
- 4" for anchor in "B" set of hardware
- 6" for anchor in "C" set of hardware
- 7" for anchor in "D" set of hardware

(22-1 - SIGNIFY CABINET INSTALL

After holes are drilled, remove template and blow out each drilled hole to remove debris, using a minimum of 80 psi of oil free compressed air.




Install sign to foundation using flat washers, lock washers and socket head cap screws provided, aligning mounting plate hole locations on bottom of sign with anchors. Use level to ensure sign is level/plumb. Shims (not provided) may be required to level sign if foundation is not level. For a clean finish, ensure shims are not showing. Optionally, grout under flange.




Place protective bib around outside of hole to protect against concrete damage from adhesive spill out. For dry or damp hole conditions, fill hole 1/2 to 2/3 full with SETPAC-EZ adhesive, starting from bottom, to prevent air pockets. For water conditions, fill hole completely with adhesive, starting from bottom, to prevent water pockets. Next, insert clean oil-free anchor into hole, turning slowly until anchor sits just below flush. Wipe off excess adhesive protruding from hole. Repeat process for remaining anchors.

Caution: Anchor must not protrude from the hole or it will interfere with mounting flange on bottom of sign.



Remove fingerprints using mild non-abrasive household cleaning agents, such as water and mild liquid dish soap. An adequate rinse should follow cleaning to assure cleansing of finish. Dilute the cleaning solution so as not to harm grass and shrubbery.



*Important: When installing sign, it must be aligned and centered to foundation and surrounding design elements (ex: sidewalks, curbs, building fascia).